


SHEET NOTES

- 1 CONTRACTOR TO PROVIDE APS WIRING. CITY FORCES TO PROVIDE APS PUSH BUTTON PER ADA REQUIREMENTS.
- 2 CONTRACTOR TO [AB] LOOP DETECTORS. CITY FORCES TO INSTALL WIRELESS SENSYS DETECTORS IN PLACE OF LOOP DETECTORS.
- 3 [AB] PER CALTRANS STANDARD SPECIFICATIONS.
- 4 [RC] EXISTING POLE, FOUNDATION, EQUIPMENT, ASSOCIATED CONDUIT, AND PULLBOX.
- 5 COORDINATE WITH SFPUC FOR REMOVAL OF PG&E STREET LIGHT POLE.
- 6 CONTACT SFMTA SIGNAL SHOP 5 DAYS PRIOR TO CONSTRUCTION TO [RS] GTT TRANSIT SIGNAL PRIORITY RADIO EQUIPMENT.
- 7 TRIM TREE UNDER SUPERVISION OF SFPW URBAN FORESTRY AT (415) 554-6700 FOR INSTALLATION AND VISIBILITY OF TRAFFIC SIGNAL/LIGHTING EQUIPMENT. THIS WORK SHALL BE CONSIDERED INCIDENTAL.
- 8 CALL SFPUC: (415) 260-9154 TO COORDINATE REMOVAL OF PULLBOX AT SE CORNER DEMOLITION CURB RAMP.
- 9 [RC] TRAFFIC SIGNAL EQUIPMENT ON EXISTING STREET LIGHT POLE.
- 10 PROVIDE CONTROLLER FOUNDATION PAD MODEL 332L PER CALTRANS STANDARD PLANS. COORDINATE WITH SFMTA FOR PICK UP OF I/C CABINET AND FOR CITY INSTALLED I/C CONTROLLER.
- 11 [RS] EXISTING CABINET AND CONTROLLER, [RC] FOUNDATION, ASSOCIATED CONDUITS AND PULLBOXES.
- 12 2 WEEKS PRIOR TO CONSTRUCTION, NOTIFY CALTRANS TO MARK THE ESA CONSTRUCTION LIMITS NEAR THE ENTRANCES OF STERN GROVE AND PINE LAKE PARK.

Pole	Base Plate Data				Cage Size	Foundation Size
	Plate Size	Bolt Circle	Thickness	Anchor Bolt Size		
PPB	7"	7"	1/2"	5/8"x12"	No Cage	18"x18"
1A	9.5"	8.5"	3/4"	1"x36"	No Cage	30"x6'
15TS	13.5"	12"	2"	1.5"x42"	24"x7'	30"x7'6"
19-2-100	22"	20"	2.5"	2"x42"	36" x 9'6"	42"x10'



NO.	DATE	DESCRIPTION	BY	APP.
TABLE OF REVISIONS				
THIS DRAWING WAS LAST MODIFIED: 12/19/18 14:39, BY: dgargaritano				


REFERENCE INFORMATION
& FILE NO. OF SURVEYS



BUREAU OF ENGINEERING
CITY & COUNTY OF SAN FRANCISCO
SAN FRANCISCO PUBLIC WORKS
30 VAN NESS AVENUE, 5TH FLOOR
SAN FRANCISCO, CA 94102 - 6028

Acting Section Mgr:	PHILIP THWIN	Date:	12/11/19
Deputy Bureau Mgr:	FERNANDO CISNEROS	Date:	12/16/19
Acting Bureau Mgr:	IQBAL DHAPA	Date:	12/16/19

DESIGNED:	DATE:
KS/DG	02/2018
DRAWN:	DATE:
KS/DG	02/2018
CHECKED:	DATE:
MV/SL	02/2018



PLAN APPROVAL DATE	CONTRACT No.	PROJECT ID	DISTRICT	COUNTY	ROUTE	POST MILES TOTAL PROJECT
	04-0G3501	0400000325	04	SF	1	R0.94/4.05
SCALE: AS SHOWN						
SHEET OF SHEETS 104 OF 356						
19TH AVENUE (STATE ROUTE 1) COMBINED CITY PROJECT						
19TH AVENUE AND WAWONA STREET						
CONTRACT NO. 1000005832						
DRAWING NO. E-6.0						
FILE NO. 111,401						
REV. NO.						