BID ITEM:

E-1 (x3)

E-4 (x1)

E-5 (x1)

E-9 (x3)

E-10 (x3)

E-11 (x3)

E-12 (x2)

E-13 (x1)

Ø41 1 Ø4APS

5/6

19TH AVE

4 RC

NO. DATE


DESCRIPTION

TABLE OF REVISIONS

THIS DRAWING WAS LAST MODIFIED: 12/19/18 14:39, BY: dgargaritano

BY APP.





Acting Section Mgr.: Deputy Bureau Mgr: FERNANDO CISNEROS Acting Bureau Mgr: **IQBAL DHAPA** CHECKED: Thapas.

1 06/08APS

SHEET NOTES

1 CONTRACTOR TO PROVIDE APS WIRING. CITY FORCES TO PROVIDE APS PUSH BUTTON PER ADA REQUIREMENTS.

2 CONTRACTOR TO AB LOOP DETECTORS. CITY FORCES TO INSTALL WIRELESS SENSYS DETECTORS IN PLACE OF LOOP DETECTORS.

3 AB PER CALTRANS STANDARD SPECIFICATIONS.

4 RC EXISTING POLE, FOUNDATION, EQUIPMENT, ASSOCIATED CONDUIT, AND PULLBOX.

5 COORDINATE WITH SFPUC FOR REMOVAL OF PG&E STREET LIGHT POLE.

6 CONTACT SFMTA SIGNAL SHOP 5 DAYS PRIOR TO CONSTRUCTION TO RS GTT TRANSIT SIGNAL PRIORITY RADIO EQUIPMENT.

7 TRIM TREE UNDER SUPERVISION OF SFPW URBAN FORESTRY AT (415) 554-6700 FOR INSTALLATION AND VISIBILITY OF TRAFFIC SIGNAL/LIGHTING EQUIPMENT. THIS WORK SHALL BE CONSIDERED INCIDENTAL.

8 CALL SFPUC: (415) 260-9154 TO COORDINATE REMOVAL OF PULLBOX AT SE CORNER DEMOLITION CURB RAMP.


9 RC TRAFFIC SIGNAL EQUIPMENT ON EXISTING STREET LIGHT POLE.

PROVIDE CONTROLLER FOUNDATION PAD MODEL 332L PER CALTRANS STANDARD PLANS. COORDINATE WITH SFMTA FOR PICK UP OF I/C CABINET AND FOR CITY INSTALLED I/C CONTROLLER.

11 RS EXISTING CABINET AND CONTROLLER, RC FOUNDATION, ASSOCIATED CONDUITS AND PULLBOXES.

2 WEEKS PRIOR TO CONSTRUCTION, NOTIFY CALTRANS TO MARK THE ESA CONSTRUCTION LIMITS NEAR THE ENTRANCES OF STERN GROVE AND PINE LAKE PARK.

Pole	Base Plate Data				Casa Sisa	Farmdation Cina	
	Plate Size	Bolt Circle	Thickness	Anchor Bolt Size	Cage Size	Foundation Size	
PPB	7"	7"	1/2"	5/8"x12"	No Cage	18"x18"	
1A	9.5"	8.5"	3/4"	1"x36"	No Cage	30"x6'	
15TS	13.5"	12"	2"	1.5"x42"	24"x7'	30"x7'6"	
19-2-100	22"	20"	2.5"	2"x42"	36" x 9'6"	42"x10'	



	DESCRIPTION OF THE PROPERTY OF						
PLAN APPROVAL DATE	CONTRACT No.	PROJECT ID	DISTRICT	COUNTY	ROUTE	POST MILES TOTAL PROJECT	
	04-0G3501	0400000325	04	SF	1	R0.94/4.05	
ROFESSIO.	SCALE:	1000				CONTRACT NO	

				31		NO.94/4
PROFESSION TONA	SCALE:	19TH AV	CONTRACT			
TEVEN CENTER	AC CHOWN		10000			
()h	AS SHOWN	COME	DRAWING N			
NO. E15417	SHEET OF SHEETS					FILE NO.
ELECTRICA TO	104 OF 356	19TH AVEN	NUE AND	WAWONA	STREET	111