


2652J

AUGUST 2022

NEC 19th & ULLOA

"CONCRETE BASE QUANTITIES"



NOTES:

1. BUREAU OF STREET USE AND MAPPING TO REFERENCE SURVEY MONUMENTS 294 AND BM10144, PRIOR TO CONSTRUCTION.
2. FOR FIRE ALARM ADJUSTMENTS/RELOCATIONS CONTRACTOR TO COORDINATE WITH MIKE DENNING, DEPARTMENT OF TECHNOLOGY, AT (415) 550-2718 PRIOR TO EXCAVATION.
3. REFER TO E-DWGS FOR TRAFFIC SIGNAL RELATED UTILITY ADJUSTMENTS AND/OR RELOCATIONS.
4. REFER TO WD-DWGS IN PLAN SET FOR WATER RELATED UTILITY ADJUSTMENTS AND/OR RELOCATIONS.
5. REFER TO MA-DWGS IN PLAN SET FOR AWWSS RELATED UTILITY ADJUSTMENTS AND/OR RELOCATIONS.
6. REFER TO SW-DWGS IN PLAN SET FOR SEWER RELATED UTILITY ADJUSTMENTS AND/OR RELOCATIONS.
7. ALL PRIVATE UTILITIES WILL BE ADJUSTED BY OWNER, CONTRACTOR TO CONTACT PRIVATE UTILITY COMPANIES PRIOR TO DEMOLITION.
8. CONTRACTOR TO COORDINATE AND CONFIRM BUS SHELTER LOCATION AND RELATED WORK WITH THE CITY AND CLEAR CHANNEL REPRESENTATIVE PRIOR TO CONSTRUCTION.
9. PARKING METER (PM) REMOVAL REFER TO TRAFFIC CONTROL SPECIFICATION 01-55-252.
10. REMOVE (E) L/S AND REPLACE WITH SIDEWALK CONFORMING TO CALTRANS STANDARDS.
11. (E) ELEVATIONS ARE BASED ON SURVEY INFORMATION RECEIVED FROM SFPD ON 10/26/2018. CONTRACTOR SHALL VERIFY CONFORM ELEVATIONS IN FIELD PRIOR TO CONSTRUCTION.
12. REFER TO PD-DWGS IN PLAN SET FOR ALL PAVEMENT MARKINGS, AND STRIPING LAYOUT.
13. PG&E TO ABANDON.

REFER TO FILE NO. 111,346
REVISION 0 FOR MANAGEMENT
SIGNATURES

LEGEND:

- 2.0% NON-STANDARD DESIGN SLOPE
2.0% STANDARD DESIGN SLOPE
(2.6%) EXISTING SLOPE

TELAMON
ENGINEERING CONSULTANTS, INC.
855 FOLSOM STREET, SUITE 142
SAN FRANCISCO, CA 94107
TEL: 415-837-1336 FAX: 415-837-1354

CR-3, Concrete Base

- ① 18'x12' = 216 SF
② 11'x25' = 275 SF
③ 47'x19' = 893 SF
④ 1/2x19'x19' = 181 SF
⑤ 54'x11' = 594 SF
⑥ 1/2x16'x6' = 48 SF

TOTAL = 2,207 SF


CR-4, 12" CL2 AB
(2,207 SF x 1') ÷ 27
= 81.7 CY

19TH AVENUE
(ROUTE 1)

CALTRANS RIGHT OF WAY

ULLOA STREET

PROJECT CONTROL BASE LINE 93+00



CR-2 Hot Mix AC

- 8/10/22 = 2.98 Tons
8/17/22 = 7.98 Tons
8/17/22 = 8.01 Tons
8/18/22 = 8.40 Tons
8/18/22 = 8.37 Tons

Total = 35.74 Tons

PLAN APPROVAL DATE	CONTRACT No.	PROJECT ID	DISTRICT	COUNTY	ROUTE	POST MILES TOTAL PROJECT
	04-0G3501	0400000325	04	SF	1	R0.94/4.05

DESIGNED: DATE: DZ 12/19	SCALE: 1" = 5'	19TH AVENUE (STATE ROUTE 1) COMBINED CITY PROJECT	CONTRACT ID: 1000005832
DRAWN: DATE: KN 12/19	SHEET OF SHEETS: 49 OF 356	19TH AVENUE AND ULLOA STREET CONSTRUCTION DETAILS	DRAWING NO: C-15A
CHECKED: DATE: MC 12/19			FILE NO: 111,346
			REV. NO: 1

NO.	DATE	ADDED SLOPE FIGURES	JM	CY
1	1/20			
TABLE OF REVISIONS				
THIS DRAWING WAS LAST MODIFIED: 12/11/19 22:43, BY: TECAAdmin				

REFERENCE INFORMATION
& FILE NO. OF SURVEYS

BUREAU OF ENGINEERING
CITY & COUNTY OF SAN FRANCISCO
SAN FRANCISCO PUBLIC WORKS
30 VAN NESS AVENUE, 5TH FLOOR
SAN FRANCISCO, CA 94102 - 6028

Acting Section Mgr	ERIC KJELSBERG	Date
Deputy Bureau Mgr	FERNANDO CISNEROS	
Acting Bureau Mgr	IOBAL DHAPA	

DESIGNED	DATE
DZ	12/19
DRAWN	DATE
KN	12/19
CHECKED	DATE
MC	12/19



SCALE	1" = 5'
SHEET OF SHEETS	49 OF 356

CONTRACT ID	1000005832
DRAWING NO	C-15A
FILE NO	111,346
REV. NO	1

Drawn: P:\15045_19th Avenue Curb Ramps\3.0.dwg, Login: TECAAdmin
Plot Date: Fri, 24 Jan 2020 - 2:45pm
P:\15045_19th Avenue Curb Ramps\3.0.dwg, Login: TECAAdmin
P:\15045_19th Avenue Curb Ramps\3.0.dwg, Login: TECAAdmin

Dimension Scale: 10
Model Units: UndefinedDrawing Path: P:\15045_19th Avenue Curb Ramps\3.0.dwg, Login: TECAAdmin
Plot Date: Fri, 24 Jan 2020 - 2:45pm