

APRIL 2022

SHt 2 of 2

CR-10, 6" Curb
250'


CR-6, 6" Thk, Glass II Aggregate Subbase
CR-5, Bus Pad - $(1,500 \text{ sf} \times 0.5') \div 27 = 27.8 \text{ CY}$
CR-7, 3 1/2" Sidewalk - $(2,556 \text{ sf} \times 0.5') \div 27 = 47.3 \text{ CY}$
CR-9, 6" Sidewalk - $(315 \text{ sf} \times 0.5') \div 27 = 5.8 \text{ CY}$
CR-10, 6" Curb - $(250' \times 0.5' \times 0.5') \div 27 = 2.3 \text{ CY}$
CR-11, Parking strip & gutter - $(412 \text{ sf} \times 0.5') \div 27 = 7.6 \text{ CY}$
Total = 90.8 CY

KEY MAP
SCALE: N.T.S.



NOTES:

- BUREAU OF STREET USE AND MAPPING TO REFERENCE SURVEY MONUMENTS 294 AND BM10144, PRIOR TO CONSTRUCTION.
- FOR FIRE ALARM ADJUSTMENTS/RELOCATIONS CONTRACTOR TO COORDINATE WITH MIKE DENNING, DEPARTMENT OF TECHNOLOGY, AT (415) 550-2718 PRIOR TO EXCAVATION.
- REFER TO E-DWGS FOR TRAFFIC SIGNAL RELATED UTILITY ADJUSTMENTS AND/OR RELOCATIONS.
- REFER TO WD-DWGS IN PLAN SET FOR WATER RELATED UTILITY ADJUSTMENTS AND/OR RELOCATIONS.
- REFER TO MA-DWGS IN PLAN SET FOR AWSS RELATED UTILITY ADJUSTMENTS AND/OR RELOCATIONS.
- REFER TO SW-DWGS IN PLAN SET FOR SEWER RELATED UTILITY ADJUSTMENTS AND/OR RELOCATIONS.
- ALL PRIVATE UTILITIES WILL BE ADJUSTED BY OWNER, CONTRACTOR TO CONTACT PRIVATE UTILITY COMPANIES PRIOR TO DEMOLITION.
- CONTRACTOR TO COORDINATE AND CONFIRM BUS SHELTER LOCATION AND RELATED WORK WITH THE CITY AND CLEAR CHANNEL REPRESENTATIVE PRIOR TO CONSTRUCTION.
- PARKING METER (PM) REMOVAL REFER TO TRAFFIC CONTROL SPECIFICATION 01-55-252.
- REMOVE (E) L/S AND REPLACE WITH SIDEWALK CONFORMING TO CALTRANS STANDARDS.
- (E) ELEVATIONS ARE BASED ON SURVEY INFORMATION RECEIVED FROM SFPD ON 10/26/2018. CONTRACTOR SHALL VERIFY CONFORM ELEVATIONS IN FIELD PRIOR TO CONSTRUCTION.
- REFER TO PD-DWGS IN PLAN SET FOR ALL PAVEMENT MARKINGS AND STRIPING LAYOUT.



CR-11, Parking Strip/Gutter
 I 35' x 7' = 245 sf
 II 1/2' x 14' x 5' = 35 sf
 III 2' x 14' = 28 sf
 IV 52' x 2' = 104 sf
 Total = 412 SF

SWC 19th & Taraval

TELAMON
ENGINEERING CONSULTANTS, INC.
855 FOLSOM STREET, SUITE 142
SAN FRANCISCO, CA 94107
TEL: 415-837-1336 FAX: 415-837-1354

NO	DATE	DESCRIPTION	BY	APP.

THIS DRAWING WAS LAST MODIFIED: 12/12/19 09:04, BY: Doug


REFERENCE INFORMATION
& FILE NO. OF SURVEYS



BUREAU OF ENGINEERING
CITY & COUNTY OF SAN FRANCISCO
SAN FRANCISCO PUBLIC WORKS
30 VAN NESS AVENUE, 5TH FLOOR
SAN FRANCISCO, CA 94102 - 6028

Acting Section Mgr.	Date	DESIGNED:	DATE:
Eric Kjellberg	12/13/19	DZ	12/19
Deputy Bureau Mgr.	DATE:	DRAWN:	DATE:
Fernando Cisneros	12/16/19	KN	12/19
Acting Bureau Mgr.	DATE:	CHECKED:	DATE:
Iqbal Dhafa	12/16/19	MC	12/19

PROFESSIONAL SEAL
ERIC KJELLBERG
CIVIL
No. 40884
Exp. 6/30/21
STATE OF CALIFORNIA

PLAN APPROVAL DATE	CONTRACT No.	PROJECT ID	DISTRICT	COUNTY	ROUTE	POST MILES TOTAL PROJECT
	04-0G3501	0400000325	04	SF	1	R0.94/4.05
	SCALE:	19TH AVENUE (STATE ROUTE 1) COMBINED CITY PROJECT				CONTRACT ID. 1000005832
	1" = 5'					DRAWING NO. C-16D
	SHEET OF SHEETS	19TH AVENUE AND TARAVAL STREET CONSTRUCTION DETAILS				FILE NO. 111,351
	54 OF 356					REV. NO

Drawing Path: P:\15045_19th Avenue Curb Ramps\3_Dwg\CR-16D.dwg, Logon: Doug
 Plot Time: Thu, 12 Dec 2019 - 12:16pm
 Measurement Units are English
 Dimension Scale: 5
 Map Units: Feet
 Xrefs: P:\15045_19th Avenue Curb Ramps\3_Dwg\Xrefs\X-TLB-2652.dwg
 P:\15045_19th Avenue Curb Ramps\3_Dwg\Xrefs\X-CS-2652-ALGN.dwg
 P:\15045_19th Avenue Curb Ramps\3_Dwg\Xrefs\X-NOTE-055C.dwg
 P:\15045_19th Avenue Curb Ramps\3_Dwg\Xrefs\X-DSCN-19th Ave Caltrans ROW Line.dwg