

CONDUIT

1 F/I 1-2" GRS; WIRING PER SHEET NOTE 2.

SHEET NOTES

1. CONTRACTOR TO PROVIDE APS WIRING. CITY FORCES TO PROVIDE APS PUSH BUTTON PER ADA REQUIREMENTS.
2. PROVIDE NEW WIRING TO MATCH EXISTING WIRING AND QUANTITY BACK TO CONTROLLER WITHOUT SPLICING. IF EXISTING WIRING HAS ENOUGH SLACK, CONTRACTOR HAS OPTION TO REUSE WITH SFMTA APPROVAL.
3. REUSE AND RL EXISTING MAST ARM POLE AS INDICATED BY POLE J ON NEW FOUNDATION. RL EXISTING STREET LIGHT FIXTURE. RC EXISTING TRAFFIC SIGNAL EQUIPMENT, MOUNTINGS, ASSOCIATED CONDUIT, AND FOUNDATION. PROVIDE NEW TRAFFIC SIGNALS AND MOUNTINGS PER POLE AND EQUIPMENT SCHEDULE. PROVIDE TEMPORARY SIGNAL AND LIGHTING AS REQUIRED.
4. ADJUST POLE TO FINISHED GRADE. COUPLE AND EXTEND ANCHOR BOLTS PER REVISED CALTRANS STANDARD PLANS RSP ES-7B DETAIL C.

POLE AND EQUIPMENT SCHEDULE (EXISTING POLE AND EQUIPMENT UNLESS OTHERWISE NOTED)

POLE	STANDARD			VEHICLE SIGNAL			PEDESTRIAN SIGNAL			APS	FIXTURE TYPE	SPECIAL REQUIREMENT
	TYPE	SMA	LMA	No.	TYPE	MOUNTING	No.	TYPE	MOUNTING			
A	19-2-100	20	8	81 84	3S12" 3S12"	SV-1-T MAS	88	1S-COUNT	SP-1-T	ø6P	108 (LED)	BACKPLATE
B	PBA POST (5')	–	–	–	–	–	–	–	–	ø8P	–	–
C	15TS	–	8	65	3S12"	SV-1-T	69	1S-COUNT	SP-1-T	–	108 (LED)	BACKPLATE
D	19-4-100	25	8	21 24	3S12" 3S12"	SV-2-T MAS	28	1S-COUNT	SP-1-T	–	108 (LED)	BACKPLATE
E	PBA POST (5')	–	–	–	–	–	–	–	–	ø8P	–	–
F	1-A(10')	–	–	85	3S12"	TV-2-T	89	1S-COUNT	SP-1-T	ø2P	–	BACKPLATE
G	17-2-100	20	8	41 44	3S12" 3S12"	SV-1-T MAS	48	1S-COUNT	SP-1-T	ø2P	108 (LED)	BACKPLATE
H	15TS	–	8	25	3S12"	SV-1-T	29	1S-COUNT	SP-1-T	ø4P	108 (LED)	BACKPLATE
I	1-A(10')	–	–	61	3S12"	TV-1-T	68	1S-COUNT	SP-1-T	ø4P	–	BACKPLATE
J	24-4-100	35	15	45 64	3S12" 3S12"	SV-1-T MAS	49	1S-COUNT	SP-1	Ø6P	108 (LED)	BACKPLATE

PHASE DIAGRAM: (STEADY DEMAND)



PHASE 2 & 6 — PHASE 4 & 8

10 0 10 20
SCALE: 1"=10'-0"

PLAN APPROVAL DATE	CONTRACT No.	PROJECT ID	DISTRICT	COUNTY	ROUTE	POST MILES TOTAL PROJECT
	04-0G3501	0400000325	04	SF	1	R0.94/4.05

NO.	DATE	DESCRIPTION	BY	APP.

TABLE OF REVISIONS
THIS DRAWING WAS LAST MODIFIED: 12/18/18 18:31, BY: dgarçarifaro

REFERENCE INFORMATION & FILE NO. OF SURVEYS

BUREAU OF ENGINEERING
CITY & COUNTY OF SAN FRANCISCO
SAN FRANCISCO PUBLIC WORKS
30 VAN NESS AVENUE, 5TH FLOOR
SAN FRANCISCO, CA 94102 - 6028

		Date:
Acting Section Mgr:	PHILIP THWIN	12/1/18
Deputy Bureau Mgr:	FERNANDO CISNEROS	12/16/18
Acting Bureau Mgr:	IQBAL DHAPA	12/16/18

DESIGNED:	KS/CG	DATE: 02/2018
DRAWN:	KS/CG	DATE: 02/2018
CHECKED:	MV/SL	DATE: 02/2018

REGISTERED PROFESSIONAL ENGINEER STEVEN T. LEE NO. E15417 ELECTRICAL STATE OF CALIFORNIA 12/10/18

SCALE: AS SHOWN
SHEET OF SHEETS: 121 OF 356

19TH AVENUE (STATE ROUTE 1)
COMBINED CITY PROJECT

19TH AVENUE AND LINCOLN WAY

CONTRACT NO. 1000005832
DRAWING NO. E-21.0
FILE NO. 111,418
REV. NO.

Drawing Path: V:\26524_19th_Avenue_Combined_City_Project\2_Design\Working_Drawings\EE\Current\E-21.0-Lincoln2666.dwg, Scale: 1Borgorifaro
Plot Time: Wed, 05 Dec 2018 - 6:14pm
Model Units: Underlayer
Measurement Units are English