



- SW-2-Manhole - 14ea
- SW-4-27"-48" Manhole-2ea
- SW-9-Catch Basin- 1ea
- SW-12-12" VCP -1069lf
- SW-13-12" VCP(Parking Strip) -57lf
- SW-18-24" VCP-351LF
- SW-17-21in VCP-29LF
- SW-14 - 15" VCP-74LF
- SW-29- 10" VCP Culvert - 47LF
- SW-32-SS Pre-TV - 64ea
- SW-36-Side Sewer Connection - 32ea
- SW-39-Vent Trap-5ea
- SW-41-Post CCTV of New Side Sewer/Culvert-7ea
- SW-37-Repalce 6" Side Sewer - 112LF
- SW-6 - Clean and Mortar Manhole - 5ea
- SW-22 CIPP 12" - 2023'
- SW-24 - CIPP 18"
- SW-25 - CIPP 21" - 46
- SW-26 - CIPP 2'x3' - 338

NOTE:

1. PRIOR TO LINING THE MAIN SEWER OR RECONNECTING SS TO THE NEWLY INSTALLED MAIN SEWER, CONTRACTOR SHALL INVESTIGATE AND CONFIRM IF SS CONNECTIONS TO MAIN SEWER ARE ACTIVE OR ABANDONED. CONTRACTOR SHALL NOT REINSTATE OR RECONNECT ANY INACTIVE SS CONNECTIONS TO THE LINED OR NEWLY INSTALLED MAIN SEWERS.

PLAN
SCALE: 1"=20'

SEWER SIZED BY B.S. *BS*
APPROVED BY B.S. *BS*

20' 0 20' 40'
SCALE: 1"=20'

NO.	DATE	DESCRIPTION	BY	APP.
0	12/19	ISSUE FOR BID	BN	LW

TABLE OF REVISIONS

REFERENCE INFORMATION & FILE NO. OF SURVEYS
A-8420
A-31057.1



BUREAU OF ENGINEERING
CITY & COUNTY OF SAN FRANCISCO
SAN FRANCISCO PUBLIC WORKS
30 VAN NESS AVENUE, 5TH FLOOR
SAN FRANCISCO, CA 94102 - 6028

Section Mgr: *Lesley Wong* Date: *12/12/19*
Deputy Bureau Mgr: *Fernando Cisneros* Date: *12/16/19*
Acting Bureau Mgr: *Iqbal Dhapa* Date: *12/16/19*

ELEVATION DATUM	PLAN APPROVAL DATE	CONTRACT No.	PROJECT ID	DISTRICT	COUNTY	ROUTE	POST MILES TOTAL PROJECT
NAVD88		04-0G3501	0400000325	04	SF	1	R0.94/4.05
DESIGNED: B.NG	DATE: 12/20/19	SCALE: AS SHOWN	19TH AVENUE (STATE ROUTE 1) COMBINED CITY PROJECT				CONTRACT ID 1000005832
DRAWN: S.LIM	DATE: 12/20/19	SHEET OF SHEETS 141 OF 356	19TH AVENUE SEWER REPLACEMENT STA 52+55 TO STA 58+55 PLAN				DRAWING NO. SW-8
CHECKED: G.FONG	DATE: 12/20/19						FILE NO. 111,439
							REV. NO. 0